

TOP SECRET

Copy 05  
4 Pages

NPIC/R-378/63  
December 1963



PHOTOGRAPHIC INTERPRETATION REPORT

# MILITARY INSTALLATIONS, BUDAPEST, HUNGARY

DECLASS REVIEW by NIMA/DOD



CIA




DIA

25X1



NATIONAL PHOTOGRAPHIC INTERPRETATION CENTER



TOP SECRET

GROUP 1  
Excluded from automatic  
downgrading and declassification

~~TOP SECRET~~

25X1

NPIC/R-378/63

### MILITARY INSTALLATIONS, BUDAPEST, HUNGARY

This report is a partial answer to DIA requirement DIAXX 63-84, to verify the location of selected military installations to determine function, number and dimensions of buildings, to estimate troop capacity, to identify and describe related training areas and facilities, and to confirm or negate ammunition or POL storage.

Photographic coverage is available on only four of the military installations in the area. The three barracks areas of the four installations have a combined troop capacity of 7,478.\* Photography of [ ] was used for analysis. [ ] photography was examined but poor quality and weather conditions preclude interpretation.

The installations described below are shown in Figures 1, 2, and 3.

#### Budapest Headquarters Soviet Forces Hungary

Coordinates: 47-30-40N 019-12-12E

BE No: [ ]

Troop capacity: 2,016

This military installation located in the east section of Budapest covers 32 acres and contains:

- 2 two-story probable barracks buildings, each 360 by 70 feet, a total of 100,800 square feet
- 2 two-story probable administration buildings, 120 by 50 and 60 by 50 feet, a total of 18,000 square feet

\*Troop capacity is computed on a basis of 50 square feet of space per man.

- 5 miscellaneous support buildings, two 160 by 50 and three 100 by 50 feet
- no observed ammunition or POL facilities.

#### Budapest Antiaircraft Artillery Barracks Stromfeld Aurel No 7

25X1D

Coordinates: 47-25-35N 019-13-52E

BE No: [ ]

Troop capacity: 3,187

This military installation located on the east edge of Budapest and one mile south of Ferihegy/Vecses Airfield covers 113 acres and contains:

- 2 three-story barracks buildings, each 240 by 60 feet
- 2 two-story barracks buildings, one 245 by 35 and one 165 by 55 feet
- 5 one-story barracks buildings, two 165 by 55, one 140 by 50, and two 125 by 50 feet, a total for the nine barracks buildings of 159,350 square feet of floor space
- 1 H-shaped administration building, the single-story base 110 by 75 feet, the three-story wing 310 by 60 feet, and the one-story wing 225 by 45 feet, a total of 74,175 square feet
- 3 storage buildings ranging from 180 by 70 to 125 by 65 feet, a total of 28,850 square feet
- 16 miscellaneous support buildings ranging from 110 by 55 to 20 by 20 feet
- a training area with a small arms firing range 390 by 35 feet
- no observed ammunition or POL facilities.

25X1D  
25X1

25X1D

~~TOP SECRET~~

25X1

25X1

Approved For Release 2002/08/26 : CIA-RDP78B04560A001000010020-5

Approved For Release 2002/08/26 : CIA-RDP78B04560A001000010020-5

NPIC/R-378/63

25X1



Budapest Army Barracks No 6

Coordinates: 47-25-30N 019-12-30E

BE No:  

Troop capacity: 2,275

This military installation located on the east edge of Budapest and 1.9 miles southwest of Ferihegy/Vecsés Airfield covers 50 acres and contains:

- 2 three-story barracks buildings, each 250 by 55 feet
- 4 single-story barracks buildings, one 130 by 50 and three 150 by 55 feet, a total for the six barracks buildings of 113,750 square feet of floor space
- 1 H-shaped administration building, the single-story base 95 by 80 feet, a three-story wing 320 by 65 feet, and a single-

- story wing 235 by 50 feet, a total of 81,750 square feet
- 4 storage buildings ranging from 100 by 50 to 50 by 30 feet, a total of 14,575 square feet
- 7 miscellaneous support buildings ranging from 60 by 35 to 25 by 25 feet
- no observed ammunition or POL facilities.

POL Storage

Coordinates: 47-20-53N 018-58-07E (UTM 34TCT471451) 47-20-25N 018-58-45E (UTM 34TCT464461)

BE No: none

Troop capacity: not applicable

Two POL storage areas are located immediately southwest of the runway at the Buda-

25X1D

TOP SECRET

25X1

NPIC/R-378/63

pest/Tokol Airfield. Each contains 4 buried cylindrical probable tanks, each approximately 50 feet in diameter.

Poor quality of available photographic coverage precluded interpretation of the following nine reported installations in the Budapest area:

military installation at 45-31-45N 019-04-30E  
military installation at 47-33-18N 019-08-13E

military installation at 47-34-06N 019-01-00E  
military installation at UTM 34TCT519681  
Soviet hospital at UTM 34TCT589669  
military installation at UTM 34TCT623628  
POL storage at UTM 34TCT5369  
tank vehicle repair at UTM 34TCT626630  
unconfirmed ammunition storage at UTM 34TCT521678.

REFERENCES

25X1D

PHOTOGRAPHY



MAPS OR CHARTS

SAC. US Air Target Chart, Series 200, Sheet 0251-1HL, 2d ed, Jun 62, scale 1:200,000 (SECRET)  
SAC. US Air Target Chart, Series 100, Sheet 0251-9997-100A, 3d ed, Nov 57, scale 1:100,000 (SECRET)

DOCUMENTS

SAC. USAF, DPIR RT55, Tokol Airfield, 20 Mar 56 (TOP SECRET  25X1

REQUIREMENT

DIAXX 63-84

NPIC PROJECT

J-252/63 (partial answer)

TOP SECRET

25X1

